DG-T01-BQ-01 Turnkey-kit BOQ and programme - Type 01 - Brick single garage

SUPPLY SCOPE: the Nudura ICF formwork + accessories (section A) are our FIXED price. Every other package (section B) is the turnkey-kit BOQ at indicative Leeds / Yorkshire Q4 2026 rates - supplied in good faith, every rate editable, to be checked by the relevant professional and priced by the contractor. All figures ex VAT unless stated. QUOTATION - NOT FOR CONSTRUCTION.
Dortech garage types - turnkey-kit BOQ rates, Leeds / Yorkshire, Q4 2026, EX VAT, net of OH&P; (applied on the BOQ). Material = supply rate per unit; labour = hours per unit x the gang rate. INDICATIVE - every rate is editable on the portal BOQ page and in the workbook. Sources: [PB] Nudura Price Book v0001 (12.10.26, Tankersley); [SAP] Tremco Dryvit SAP price export (03.07.26); [NGR] Nudura Garden Rooms engine.js DEFAULT_RATES (UK 2026 trade); [TLS] TLS Garden Rooms engine.js; [WEB] merchant prices checked 28.10.26 (Marley Modern ~GBP 1.48 + VAT each, 10.7/m2); [MKT] market rate (no source on the machine - brick slips installed GBP 120-200/m2 on EPS incl. insulation; ours is slips only on the Nudura EPS). Yorkshire factor 0.95 applied to UK labour (Leeds below the UK mean).

Labour 34.00 GBP/h | OH&P; 15.0% | contingency 10.0% - the editable version is the BOQ page on the portal and the Excel download.

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
Bill 1 - Preliminaries	Site setup, welfare, skip, setting out	1.00	item	650.00	272.00	650.00	272.00	922.00
Bill 1 - Preliminaries	Access scaffold / towers	1.00	item	480.00	136.00	480.00	136.00	616.00
Bill 2 - Groundworks + substructure	Excavate raft + thickened edge (reduce level 402 + edge to 500)	10.03	m3	18.00	11.90	180.54	119.36	299.90
Bill 2 - Groundworks + substructure	Muck away (bulked x1.25)	12.54	m3	52.00	0.00	652.08	0.00	652.08
Bill 2 - Groundworks + substructure	RWG drainage - short run to soakaway / connection	1.00	item	420.00	340.00	420.00	340.00	760.00
Bill 2 - Groundworks + substructure	MOT Type 1 hardcore 150, compacted	1.78	m3	48.00	17.00	85.44	30.26	115.70
Bill 2 - Groundworks + substructure	Sand blinding + 1200g DPM	24.32	m2	5.30	2.04	128.90	49.61	178.51
Bill 2 - Groundworks + substructure	A393 mesh top + bottom (laps incl.)	6.00	sheet	70.00	11.90	420.00	71.40	491.40
Bill 2 - Groundworks + substructure	Starter bars T12 @ 600 into the ICF + edge bars	0.10	t	1,250.00	952.00	125.00	95.20	220.20
Bill 2 - Groundworks + substructure	C32/40 raft concrete 200 + thickened edge	6.98	m3	152.00	40.80	1,060.96	284.78	1,345.74
Bill 2 - Groundworks + substructure	Concrete pump - raft pour	1.00	pour	650.00	0.00	650.00	0.00	650.00
Bill 2 - Groundworks + substructure	Power float finish (garage floor, fall to the door)	22.11	m2	1.50	2.72	33.16	60.14	93.30
Bill 3 - ICF walls (install + concrete)	Stand the Nudura forms (62 forms, 4.3 min / form): set-out, bracing + alignment, rebar, end caps / lintels	1.00	gang-day	0.00	816.00	0.00	816.00	816.00
Bill 3 - ICF walls (install + concrete)	Pour the ICF core (walls + gables, one day), 4-man pour gang	1.00	gang-day	0.00	1,088.00	0.00	1,088.00	1,088.00
Bill 3 - ICF walls (install + concrete)	Strike the bracing + alignment system (after 1 day cure)	1.00	gang-day	0.00	816.00	0.00	816.00	816.00
Bill 3 - ICF walls (install + concrete)	Wall reinforcement T12 (vertical @ 600, horizontal alternate courses) + lintel bars - supply (fixing in the install line)	0.17	t	1,250.00	0.00	212.50	0.00	212.50
Bill 3 - ICF walls (install + concrete)	C32/40 core concrete 6in - supply (placing in the install line)	5.96	m3	152.00	0.00	905.92	0.00	905.92
Bill 3 - ICF walls (install + concrete)	Concrete pump - ICF pour	1.00	pour	650.00	0.00	650.00	0.00	650.00
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Wall plate 47 x 150 C24 treated on the eaves walls (bedded)	12.15	m	5.60	8.50	68.04	103.28	171.32
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Wall plate fixings - M12 anchors into the ICF core @ 1,200 + washers	13.00	nr	3.20	5.10	41.60	66.30	107.90

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Trussed rafters (fink) @600, span 3.64 m	10.00	nr	114.41	25.50	1,144.10	255.00	1,399.10
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Binders + diagonal bracing 25 x 100	31.48	m	1.35	2.72	42.50	85.63	128.13
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Truss clips to the wall plate (2 per truss)	20.00	nr	1.10	2.72	22.00	54.40	76.40
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Twist / holding-down straps (2 per truss)	20.00	nr	1.40	3.40	28.00	68.00	96.00
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	PROVISIONAL floors / decking - 18 P5 loft storage boards on the ceiling ties (storage-rated trusses)	8.44	m2	9.50	8.50	80.18	71.74	151.92
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	PROVISIONAL - 47 x 72 noggins under the board edges	14.07	m	1.90	3.40	26.73	47.84	74.57
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	PROVISIONAL - deck screws	8.44	m2	0.60	0.00	5.06	0.00	5.06
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	PROVISIONAL - insulated loft hatch + folding ladder	1.00	nr	185.00	68.00	185.00	68.00	253.00
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Gable ladders (barge, rails, outriggers 47 x 72)	29.58	m	1.35	2.72	39.93	80.46	120.39
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Gable lateral restraint straps @ 2 m to the trusses / rafters (both gables)	8.00	nr	4.50	6.80	36.00	54.40	90.40
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Carpentry sundries - nails, screws, framing anchors	1.00	item	45.00	0.00	45.00	0.00	45.00
Bill 5 - Roof coverings + rainwater goods	Breathable roofing membrane (laps incl.)	36.20	m2	1.10	1.02	39.82	36.92	76.74
Bill 5 - Roof coverings + rainwater goods	Treated battens 25 x 50 @ 345 gauge	126.30	m	0.85	0.68	107.35	85.88	193.23
Bill 5 - Roof coverings + rainwater goods	Marley Modern smooth grey tiles (drawn: 308, +3% breakage)	318.00	nr	1.48	1.19	470.64	378.42	849.06
Bill 5 - Roof coverings + rainwater goods	Dry ridge + half-round ridge tiles (15 drawn)	6.38	m	24.00	11.90	153.12	75.92	229.04
Bill 5 - Roof coverings + rainwater goods	Dry verge units	9.86	m	14.00	6.80	138.04	67.05	205.09
Bill 5 - Roof coverings + rainwater goods	uPVC fascia + vented soffit	12.75	m	16.00	11.90	204.00	151.72	355.72
Bill 5 - Roof coverings + rainwater goods	uPVC barge boards 22 x 225	9.86	m	14.00	10.20	138.04	100.57	238.61
Bill 5 - Roof coverings + rainwater goods	Half-round gutter 112 black + fittings	12.75	m	11.00	6.80	140.25	86.70	226.95
Bill 5 - Roof coverings + rainwater goods	Downpipe sets 68 round black	2.00	nr	38.00	34.00	76.00	68.00	144.00

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
Bill 6 - External wall finish	Monolith BrickPlus slips 215 x 65 x 20 - supply + fix + point (flat area)	40.34	m2	42.00	37.40	1,694.28	1,508.72	3,203.00
Bill 6 - External wall finish	L-shaped corner slips (drawn: 240 legs)	266.00	nr	1.65	1.02	438.90	271.32	710.22
Bill 6 - External wall finish	Slip adhesive 25 kg	9.00	bag	19.50	0.00	175.50	0.00	175.50
Bill 6 - External wall finish	Pointing mortar 25 kg	7.00	bag	16.00	0.00	112.00	0.00	112.00
Bill 6 - External wall finish	Base starter track + stop trims	37.10	m	6.00	3.40	222.60	126.14	348.74
Bill 7 - Opening schedule (doors + windows)	L1-D01 Electric insulated roller garage door 2,400 x 2,286 S.O., RAL 7016: 77 slats, box behind the lintel course, guides, tubular motor, 2 remotes, manual override, brush seals	1.00	nr	1,658.37	204.00	1,658.37	204.00	1,862.37
Bill 7 - Opening schedule (doors + windows)	L1-D02 Composite personnel door 900 x 2,286 S.O.: frame, fixed overpanel, multipoint lock, lever handles, low threshold; illbruck ME110 internal membrane (5.5 m) + sealant	1.00	nr	1,067.94	184.96	1,067.94	184.96	1,252.90
Bill 7 - Opening schedule (doors + windows)	L1-W01 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant	1.00	nr	753.29	113.56	753.29	113.56	866.85
Bill 8 - Electrical installation	2 double sockets + 2 LED battens, sub-board, short feed, test + cert	1.00	item	520.00	476.00	520.00	476.00	996.00
Bill 9 - Design + approvals (provisional)	Building control (provisional)	1.00	item	650.00	0.00	650.00	0.00	650.00
Bill 9 - Design + approvals (provisional)	Structural engineer - calcs + details (provisional)	1.00	item	850.00	0.00	850.00	0.00	850.00
Bill 9 - Design + approvals (provisional)	Drawings / lawful development certificate (provisional)	1.00	item	1,250.00	0.00	1,250.00	0.00	1,250.00
							BOQ net	28,348.46

Programme - construction time per element (working days)

Element	Days	Note
Site setup + setting out	0.50	welfare, skip, set out the raft
Below ground - excavation, muck away, drainage	1.90	2 operatives + excavator
Footings / substructure - hardcore, DPM, mesh, starter bars	1.00	
Raft pour + power float	1.00	pump on site
Raft cure before the ICF	3.00	minimum before standing the forms (7 days before full load)
ICF install - stand forms, rebar, bracing + alignment	1.00	3-man gang, 4.3 min / form
ICF pour (walls + gables)	1.00	4-man pour gang + pump
ICF cure	1.00	
Strike the bracing + alignment	1.00	alignment hire = 4 working days -> 1 wk
Roof structure	1.80	trusses / rafters + ridge, ladders
Roof coverings + rainwater goods	1.90	2 roofers
Doors, windows + opening tapes	1.00	
External finish	3.50	2 operatives (slips)
Electrics + test	1.80	1 electrician

Element	Days	Note
Snag + clean	0.50	
Total	21.90	about 5 weeks