# DG-T04-BQ-01 Turnkey-kit BOQ and programme - Type 04 - Brick two-storey double

SUPPLY SCOPE: the Nudura ICF formwork + accessories (section A) are our FIXED price. Every other package (section B) is the turnkey-kit BOQ at indicative Leeds / Yorkshire Q4 2026 rates - supplied in good faith, every rate editable, to be checked by the relevant professional and priced by the contractor. All figures ex VAT unless stated. QUOTATION - NOT FOR CONSTRUCTION.
Dortech garage types - turnkey-kit BOQ rates, Leeds / Yorkshire, Q4 2026, EX VAT, net of OH&P; (applied on the BOQ). Material = supply rate per unit; labour = hours per unit x the gang rate. INDICATIVE - every rate is editable on the portal BOQ page and in the workbook. Sources: [PB] Nudura Price Book v0001 (12.10.26, Tankersley); [SAP] Tremco Dryvit SAP price export (03.07.26); [NGR] Nudura Garden Rooms engine.js DEFAULT_RATES (UK 2026 trade); [TLS] TLS Garden Rooms engine.js; [WEB] merchant prices checked 28.10.26 (Marley Modern ~GBP 1.48 + VAT each, 10.7/m2); [MKT] market rate (no source on the machine - brick slips installed GBP 120-200/m2 on EPS incl. insulation; ours is slips only on the Nudura EPS). Yorkshire factor 0.95 applied to UK labour (Leeds below the UK mean).

Labour 34.00 GBP/h | OH&P; 15.0% | contingency 10.0% - the editable version is the BOQ page on the portal and the Excel download.

| Bill | Item | Qty | Unit | Supply rate | Install rate | Supply | Install | Total |
|---|---|---|---|---|---|---|---|---|
| Bill 1 - Preliminaries | Site setup, welfare, skip, setting out | 1.00 | item | 650.00 | 272.00 | 650.00 | 272.00 | 922.00 |
| Bill 1 - Preliminaries | Access scaffold / towers | 32.77 | m | 38.00 | 0.00 | 1,245.26 | 0.00 | 1,245.26 |
| Bill 2 - Groundworks + substructure | Excavate raft + thickened edge (reduce level 402 + edge to 500) | 21.19 | m3 | 18.00 | 11.90 | 381.42 | 252.16 | 633.58 |
| Bill 2 - Groundworks + substructure | Muck away (bulked x1.25) | 26.49 | m3 | 52.00 | 0.00 | 1,377.48 | 0.00 | 1,377.48 |
| Bill 2 - Groundworks + substructure | RWG drainage - short run to soakaway / connection | 1.00 | item | 420.00 | 340.00 | 420.00 | 340.00 | 760.00 |
| Bill 2 - Groundworks + substructure | MOT Type 1 hardcore 150, compacted | 4.99 | m3 | 48.00 | 17.00 | 239.52 | 84.83 | 324.35 |
| Bill 2 - Groundworks + substructure | Sand blinding + 1200g DPM | 53.48 | m2 | 5.30 | 2.04 | 283.44 | 109.10 | 392.54 |
| Bill 2 - Groundworks + substructure | A393 mesh top + bottom (laps incl.) | 10.00 | sheet | 70.00 | 11.90 | 700.00 | 119.00 | 819.00 |
| Bill 2 - Groundworks + substructure | Starter bars T12 @ 600 into the ICF + edge bars | 0.15 | t | 1,250.00 | 952.00 | 187.50 | 142.80 | 330.30 |
| Bill 2 - Groundworks + substructure | C32/40 raft concrete 200 + thickened edge | 13.56 | m3 | 152.00 | 40.80 | 2,061.12 | 553.25 | 2,614.37 |
| Bill 2 - Groundworks + substructure | Concrete pump - raft pour | 1.00 | pour | 650.00 | 0.00 | 650.00 | 0.00 | 650.00 |
| Bill 2 - Groundworks + substructure | Power float finish (garage floor, fall to the door) | 48.62 | m2 | 1.50 | 2.72 | 72.93 | 132.25 | 205.18 |
| Bill 3 - ICF walls (install + concrete) | Stand the Nudura forms (201 forms, 4.3 min / form): set-out, bracing + alignment, rebar, end caps / lintels | 2.00 | gang-day | 0.00 | 816.00 | 0.00 | 1,632.00 | 1,632.00 |
| Bill 3 - ICF walls (install + concrete) | Pour the ICF core (walls + gables, one day), 4-man pour gang | 1.00 | gang-day | 0.00 | 1,088.00 | 0.00 | 1,088.00 | 1,088.00 |
| Bill 3 - ICF walls (install + concrete) | Strike the bracing + alignment system (after 1 day cure) | 1.00 | gang-day | 0.00 | 816.00 | 0.00 | 816.00 | 816.00 |
| Bill 3 - ICF walls (install + concrete) | Wall reinforcement T12 (vertical @ 600, horizontal alternate courses) + lintel bars - supply (fixing in the install line) | 0.58 | t | 1,250.00 | 0.00 | 725.00 | 0.00 | 725.00 |
| Bill 3 - ICF walls (install + concrete) | C32/40 core concrete 6in - supply (placing in the install line) | 20.52 | m3 | 152.00 | 0.00 | 3,119.04 | 0.00 | 3,119.04 |
| Bill 3 - ICF walls (install + concrete) | Concrete pump - ICF pour | 1.00 | pour | 650.00 | 0.00 | 650.00 | 0.00 | 650.00 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Wall plate 47 x 150 C24 treated on the eaves walls (bedded) | 12.97 | m | 5.60 | 8.50 | 72.63 | 110.25 | 182.88 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Wall plate fixings - M12 anchors into the ICF core @ 1,200 + washers | 13.00 | nr | 3.20 | 5.10 | 41.60 | 66.30 | 107.90 |

| Bill | Item | Qty | Unit | Supply rate | Install rate | Supply | Install | Total |
|---|---|---|---|---|---|---|---|---|
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Loose C24 rafters (cut roof) | 150.51 | m | 4.60 | 6.12 | 692.35 | 921.12 | 1,613.47 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Glulam GL24h ridge beam 100 x 480 (framer pick, engineer to confirm) | 0.33 | m3 | 1,150.00 | 204.00 | 379.50 | 67.32 | 446.82 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | 304 metal-web floor joists @ 400 across the 5.91 m width (21 nr incl. doubled trimming + trimmed) | 124.15 | m | 17.50 | 4.76 | 2,172.62 | 590.95 | 2,763.57 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | C24 ledgers on the ICF (47 x 178 side walls, 47 x 150 deck-edge on the eaves walls) | 22.03 | m | 6.20 | 10.20 | 136.59 | 224.71 | 361.30 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Simpson ICFVL-CW + ICFLC ledger connectors, cast into the ICF @ <= 1,200 | 23.00 | nr | 9.80 | 5.10 | 225.40 | 117.30 | 342.70 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Joist hangers + top-chord restraint clips (trimmed joists, trimmer, doubled joists) | 50.00 | nr | 4.20 | 5.10 | 210.00 | 255.00 | 465.00 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | 22 Egger Protect P5 T&G; deck, glued + screwed | 40.41 | m2 | 12.50 | 8.50 | 505.12 | 343.48 | 848.60 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Straight timber stair to AD K - 14 risers x 196 / 230, 900 wide (joinery manufacturer) | 1.00 | nr | 1,150.00 | 408.00 | 1,150.00 | 408.00 | 1,558.00 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | 900 guarding round the stair well on the first floor | 3.65 | m | 85.00 | 40.80 | 310.25 | 148.92 | 459.17 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Garage ceiling - 12.5 fire-rated plasterboard + skim (30 min under the room, BC to confirm) | 38.49 | m2 | 9.00 | 15.30 | 346.41 | 588.90 | 935.31 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Gable ladders (barge, rails, outriggers 47 x 72) | 54.73 | m | 1.35 | 2.72 | 73.89 | 148.87 | 222.76 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Gable lateral restraint straps @ 2 m to the trusses / rafters (both gables) | 12.00 | nr | 4.50 | 6.80 | 54.00 | 81.60 | 135.60 |
| Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings) | Carpentry sundries - nails, screws, framing anchors | 1.00 | item | 45.00 | 0.00 | 45.00 | 0.00 | 45.00 |
| Bill 5 - Roof coverings + rainwater goods | Breathable roofing membrane (laps incl.) | 71.20 | m2 | 1.10 | 1.02 | 78.32 | 72.62 | 150.94 |
| Bill 5 - Roof coverings + rainwater goods | Treated battens 25 x 50 @ 345 gauge | 223.90 | m | 0.85 | 0.68 | 190.31 | 152.25 | 342.56 |
| Bill 5 - Roof coverings + rainwater goods | Marley Modern smooth grey tiles (drawn: 658, +3% breakage) | 678.00 | nr | 1.48 | 1.19 | 1,003.44 | 806.82 | 1,810.26 |
| Bill 5 - Roof coverings + rainwater goods | Dry ridge + half-round ridge tiles (16 drawn) | 6.78 | m | 24.00 | 11.90 | 162.72 | 80.68 | 243.40 |
| Bill 5 - Roof coverings + rainwater goods | Dry verge units | 18.24 | m | 14.00 | 6.80 | 255.36 | 124.03 | 379.39 |
| Bill 5 - Roof coverings + rainwater goods | uPVC fascia 22 x 300 + vented soffit | 13.57 | m | 16.00 | 11.90 | 217.12 | 161.48 | 378.60 |

| Bill | Item | Qty | Unit | Supply rate | Install rate | Supply | Install | Total |
|---|---|---|---|---|---|---|---|---|
| Bill 5 - Roof coverings + rainwater goods | uPVC barge boards 22 x 325 | 18.24 | m | 14.00 | 10.20 | 255.36 | 186.05 | 441.41 |
| Bill 5 - Roof coverings + rainwater goods | Half-round gutter 112 black + fittings | 13.57 | m | 11.00 | 6.80 | 149.27 | 92.28 | 241.55 |
| Bill 5 - Roof coverings + rainwater goods | Downpipe sets 68 round black: swan neck to the outlet, clipped to the side wall (8 clips), shoe | 2.00 | nr | 38.00 | 34.00 | 76.00 | 68.00 | 144.00 |
| Bill 6 - External wall finish | Monolith BrickPlus slips 215 x 65 x 20 - supply + fix + point (flat area) | 138.83 | m2 | 42.00 | 37.40 | 5,830.86 | 5,192.24 | 11,023.10 |
| Bill 6 - External wall finish | L-shaped corner slips (drawn: 528 legs) | 533.00 | nr | 1.65 | 1.02 | 879.45 | 543.66 | 1,423.11 |
| Bill 6 - External wall finish | Slip adhesive 25 kg | 29.00 | bag | 19.50 | 0.00 | 565.50 | 0.00 | 565.50 |
| Bill 6 - External wall finish | Pointing mortar 25 kg | 23.00 | bag | 16.00 | 0.00 | 368.00 | 0.00 | 368.00 |
| Bill 6 - External wall finish | Base starter track + stop trims | 52.30 | m | 6.00 | 3.40 | 313.80 | 177.82 | 491.62 |
| Bill 7 - Opening schedule (doors + windows) | L1-D01 Electric insulated roller garage door 4,800 x 2,286 S.O., RAL 7016: 77 slats, box behind the lintel course, guides, tubular motor, 2 remotes, manual override, brush seals | 1.00 | nr | 2,461.25 | 272.00 | 2,461.25 | 272.00 | 2,733.25 |
| Bill 7 - Opening schedule (doors + windows) | L1-D02 Composite personnel door 900 x 2,286 S.O.: frame, fixed overpanel, multipoint lock, lever handles, low threshold; illbruck ME110 internal membrane (5.5 m) + sealant | 1.00 | nr | 1,067.94 | 184.96 | 1,067.94 | 184.96 | 1,252.90 |
| Bill 7 - Opening schedule (doors + windows) | L1-W01 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant | 1.00 | nr | 753.29 | 113.56 | 753.29 | 113.56 | 866.85 |
| Bill 7 - Opening schedule (doors + windows) | L1-W02 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant | 1.00 | nr | 753.29 | 113.56 | 753.29 | 113.56 | 866.85 |
| Bill 7 - Opening schedule (doors + windows) | L1-W11 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant | 1.00 | nr | 753.29 | 113.56 | 753.29 | 113.56 | 866.85 |
| Bill 7 - Opening schedule (doors + windows) | L1-W12 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant | 1.00 | nr | 753.29 | 113.56 | 753.29 | 113.56 | 866.85 |
| Bill 7 - Opening schedule (doors + windows) | L1-W13 Alu-clad timber window 900 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (3.6 m) + sealant | 1.00 | nr | 636.46 | 111.86 | 636.46 | 111.86 | 748.32 |
| Bill 7 - Opening schedule (doors + windows) | L1-W14 Alu-clad timber window 600 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (3.0 m) + sealant | 1.00 | nr | 519.65 | 110.16 | 519.65 | 110.16 | 629.81 |
| Bill 8 - Electrical installation | 4 double sockets + 4 LED battens, sub-board, short feed, test + cert | 1.00 | item | 760.00 | 680.00 | 760.00 | 680.00 | 1,440.00 |
| Bill 9 - Design + approvals (provisional) | Building control (provisional) | 1.00 | item | 650.00 | 0.00 | 650.00 | 0.00 | 650.00 |
| Bill 9 - Design + approvals (provisional) | Structural engineer - calcs + details (provisional) | 1.00 | item | 850.00 | 0.00 | 850.00 | 0.00 | 850.00 |
| Bill 9 - Design + approvals (provisional) | Drawings / lawful development certificate (provisional) | 1.00 | item | 1,250.00 | 0.00 | 1,250.00 | 0.00 | 1,250.00 |
| | | | | | | | BOQ net | 59,817.30 |

### *Programme - construction time per element (working days)*

| Element | Days | Note |
|---|---|---|
| Site setup + setting out | 0.50 | welfare, skip, set out the raft |
| Below ground - excavation, muck away, drainage | 3.20 | 2 operatives + excavator |
| Footings / substructure - hardcore, DPM, mesh, starter bars | 1.00 | |
| Raft pour + power float | 1.00 | pump on site |
| Raft cure before the ICF | 3.00 | minimum before standing the forms (7 days before full load) |
| ICF install - stand forms, rebar, bracing + alignment | 2.00 | 3-man gang, 4.3 min / form |
| ICF pour (walls + gables) | 1.00 | 4-man pour gang + pump |
| ICF cure | 1.00 | |
| Strike the bracing + alignment | 1.00 | alignment hire = 5 working days -> 1 wk |
| First floor, stair + roof structure | 7.50 | joists, deck, stair, guarding, ceiling; rafters + glulam ridge, ladders |
| Roof coverings + rainwater goods | 3.20 | 2 roofers |
| Doors, windows + opening tapes | 2.10 | |
| External finish | 10.90 | 2 operatives (slips) |
| Electrics + test | 2.50 | 1 electrician |
| Snag + clean | 0.50 | |
| Total | 40.40 | about 9 weeks |