DG-T08-BQ-01 Turnkey-kit BOQ and programme - Type 08 - Rendered two-storey double

SUPPLY SCOPE: the Nudura ICF formwork + accessories (section A) are our FIXED price. Every other package (section B) is the turnkey-kit BOQ at indicative Leeds / Yorkshire Q4 2026 rates - supplied in good faith, every rate editable, to be checked by the relevant professional and priced by the contractor. All figures ex VAT unless stated. QUOTATION - NOT FOR CONSTRUCTION.
Dortech garage types - turnkey-kit BOQ rates, Leeds / Yorkshire, Q4 2026, EX VAT, net of OH&P; (applied on the BOQ). Material = supply rate per unit; labour = hours per unit x the gang rate. INDICATIVE - every rate is editable on the portal BOQ page and in the workbook. Sources: [PB] Nudura Price Book v0001 (12.10.26, Tankersley); [SAP] Tremco Dryvit SAP price export (03.07.26); [NGR] Nudura Garden Rooms engine.js DEFAULT_RATES (UK 2026 trade); [TLS] TLS Garden Rooms engine.js; [WEB] merchant prices checked 28.10.26 (Marley Modern ~GBP 1.48 + VAT each, 10.7/m2); [MKT] market rate (no source on the machine - brick slips installed GBP 120-200/m2 on EPS incl. insulation; ours is slips only on the Nudura EPS). Yorkshire factor 0.95 applied to UK labour (Leeds below the UK mean).

Labour 34.00 GBP/h | OH&P; 15.0% | contingency 10.0% - the editable version is the BOQ page on the portal and the Excel download.

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
Bill 1 - Preliminaries	Site setup, welfare, skip, setting out	1.00	item	650.00	272.00	650.00	272.00	922.00
Bill 1 - Preliminaries	Access scaffold / towers	32.77	m	38.00	0.00	1,245.26	0.00	1,245.26
Bill 2 - Groundworks + substructure	Excavate raft + thickened edge (reduce level 402 + edge to 500)	21.19	m3	18.00	11.90	381.42	252.16	633.58
Bill 2 - Groundworks + substructure	Muck away (bulked x1.25)	26.49	m3	52.00	0.00	1,377.48	0.00	1,377.48
Bill 2 - Groundworks + substructure	RWG drainage - short run to soakaway / connection	1.00	item	420.00	340.00	420.00	340.00	760.00
Bill 2 - Groundworks + substructure	MOT Type 1 hardcore 150, compacted	4.99	m3	48.00	17.00	239.52	84.83	324.35
Bill 2 - Groundworks + substructure	Sand blinding + 1200g DPM	53.48	m2	5.30	2.04	283.44	109.10	392.54
Bill 2 - Groundworks + substructure	A393 mesh top + bottom (laps incl.)	10.00	sheet	70.00	11.90	700.00	119.00	819.00
Bill 2 - Groundworks + substructure	Starter bars T12 @ 600 into the ICF + edge bars	0.15	t	1,250.00	952.00	187.50	142.80	330.30
Bill 2 - Groundworks + substructure	C32/40 raft concrete 200 + thickened edge	13.56	m3	152.00	40.80	2,061.12	553.25	2,614.37
Bill 2 - Groundworks + substructure	Concrete pump - raft pour	1.00	pour	650.00	0.00	650.00	0.00	650.00
Bill 2 - Groundworks + substructure	Power float finish (garage floor, fall to the door)	48.62	m2	1.50	2.72	72.93	132.25	205.18
Bill 3 - ICF walls (install + concrete)	Stand the Nudura forms (201 forms, 4.3 min / form): set-out, bracing + alignment, rebar, end caps / lintels	2.00	gang-day	0.00	816.00	0.00	1,632.00	1,632.00
Bill 3 - ICF walls (install + concrete)	Pour the ICF core (walls + gables, one day), 4-man pour gang	1.00	gang-day	0.00	1,088.00	0.00	1,088.00	1,088.00
Bill 3 - ICF walls (install + concrete)	Strike the bracing + alignment system (after 1 day cure)	1.00	gang-day	0.00	816.00	0.00	816.00	816.00
Bill 3 - ICF walls (install + concrete)	Wall reinforcement T12 (vertical @ 600, horizontal alternate courses) + lintel bars - supply (fixing in the install line)	0.58	t	1,250.00	0.00	725.00	0.00	725.00
Bill 3 - ICF walls (install + concrete)	C32/40 core concrete 6in - supply (placing in the install line)	20.52	m3	152.00	0.00	3,119.04	0.00	3,119.04
Bill 3 - ICF walls (install + concrete)	Concrete pump - ICF pour	1.00	pour	650.00	0.00	650.00	0.00	650.00
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Wall plate 47 x 150 C24 treated on the eaves walls (bedded)	12.97	m	5.60	8.50	72.63	110.25	182.88
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Wall plate fixings - M12 anchors into the ICF core @ 1,200 + washers	13.00	nr	3.20	5.10	41.60	66.30	107.90

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Loose C24 rafters (cut roof)	150.51	m	4.60	6.12	692.35	921.12	1,613.47
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Glulam GL24h ridge beam 100 x 480 (framer pick, engineer to confirm)	0.33	m3	1,150.00	204.00	379.50	67.32	446.82
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	304 metal-web floor joists @ 400 across the 5.91 m width (21 nr incl. doubled trimming + trimmed)	124.15	m	17.50	4.76	2,172.62	590.95	2,763.57
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	C24 ledgers on the ICF (47 x 178 side walls, 47 x 150 deck-edge on the eaves walls)	22.03	m	6.20	10.20	136.59	224.71	361.30
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Simpson ICFVL-CW + ICFLC ledger connectors, cast into the ICF @ <= 1,200	23.00	nr	9.80	5.10	225.40	117.30	342.70
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Joist hangers + top-chord restraint clips (trimmed joists, trimmer, doubled joists)	50.00	nr	4.20	5.10	210.00	255.00	465.00
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	22 Egger Protect P5 T&G; deck, glued + screwed	40.41	m2	12.50	8.50	505.12	343.48	848.60
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Straight timber stair to AD K - 14 risers x 196 / 230, 900 wide (joinery manufacturer)	1.00	nr	1,150.00	408.00	1,150.00	408.00	1,558.00
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	900 guarding round the stair well on the first floor	3.65	m	85.00	40.80	310.25	148.92	459.17
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Garage ceiling - 12.5 fire-rated plasterboard + skim (30 min under the room, BC to confirm)	38.49	m2	9.00	15.30	346.41	588.90	935.31
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Gable ladders (barge, rails, outriggers 47 x 72)	54.73	m	1.35	2.72	73.89	148.87	222.76
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Gable lateral restraint straps @ 2 m to the trusses / rafters (both gables)	12.00	nr	4.50	6.80	54.00	81.60	135.60
Bill 4 - Roof structure + floors (carpentry: supply + install incl. fixings)	Carpentry sundries - nails, screws, framing anchors	1.00	item	45.00	0.00	45.00	0.00	45.00
Bill 5 - Roof coverings + rainwater goods	Breathable roofing membrane (laps incl.)	71.20	m2	1.10	1.02	78.32	72.62	150.94
Bill 5 - Roof coverings + rainwater goods	Treated battens 25 x 50 @ 345 gauge	223.90	m	0.85	0.68	190.31	152.25	342.56
Bill 5 - Roof coverings + rainwater goods	Marley Modern smooth grey tiles (drawn: 658, +3% breakage)	678.00	nr	1.48	1.19	1,003.44	806.82	1,810.26
Bill 5 - Roof coverings + rainwater goods	Dry ridge + half-round ridge tiles (16 drawn)	6.78	m	24.00	11.90	162.72	80.68	243.40
Bill 5 - Roof coverings + rainwater goods	Dry verge units	18.24	m	14.00	6.80	255.36	124.03	379.39
Bill 5 - Roof coverings + rainwater goods	uPVC fascia 22 x 300 + vented soffit	13.57	m	16.00	11.90	217.12	161.48	378.60

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
Bill 5 - Roof coverings + rainwater goods	uPVC barge boards 22 x 325	18.24	m	14.00	10.20	255.36	186.05	441.41
Bill 5 - Roof coverings + rainwater goods	Half-round gutter 112 black + fittings	13.57	m	11.00	6.80	149.27	92.28	241.55
Bill 5 - Roof coverings + rainwater goods	Downpipe sets 68 round black: swan neck to the outlet, clipped to the side wall (8 clips), shoe	2.00	nr	38.00	34.00	76.00	68.00	144.00
Bill 6 - External wall finish	Dryvit Primus M base coat 25 kg	8.00	pail	23.18	0.00	185.44	0.00	185.44
Bill 6 - External wall finish	Dryvit Standard Plus mesh (laps incl.)	162.12	m2	1.33	0.00	215.62	0.00	215.62
Bill 6 - External wall finish	Dryvit Color Prime Plus 4 gal	6.00	pail	51.79	0.00	310.74	0.00	310.74
Bill 6 - External wall finish	Dryvit PMR Sandpebble finish 24.72 kg	13.00	pail	59.90	0.00	778.70	0.00	778.70
Bill 6 - External wall finish	Apply Dryvit 500 (base + mesh + prime + finish)	140.97	m2	0.00	25.50	0.00	3,594.74	3,594.74
Bill 6 - External wall finish	Dryvit beads (base, corner, stop, reveal)	136.60	m	1.30	1.70	177.58	232.22	409.80
Bill 7 - Opening schedule (doors + windows)	L1-D01 Electric insulated roller garage door 4,800 x 2,286 S.O., RAL 7016: 77 slats, box behind the lintel course, guides, tubular motor, 2 remotes, manual override, brush seals	1.00	nr	2,461.25	272.00	2,461.25	272.00	2,733.25
Bill 7 - Opening schedule (doors + windows)	L1-D02 Composite personnel door 900 x 2,286 S.O.: frame, fixed overpanel, multipoint lock, lever handles, low threshold; illbruck ME110 internal membrane (5.5 m) + sealant	1.00	nr	1,067.94	184.96	1,067.94	184.96	1,252.90
Bill 7 - Opening schedule (doors + windows)	L1-W01 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant	1.00	nr	753.29	113.56	753.29	113.56	866.85
Bill 7 - Opening schedule (doors + windows)	L1-W02 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant	1.00	nr	753.29	113.56	753.29	113.56	866.85
Bill 7 - Opening schedule (doors + windows)	L1-W11 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant	1.00	nr	753.29	113.56	753.29	113.56	866.85
Bill 7 - Opening schedule (doors + windows)	L1-W12 Alu-clad timber window 1,200 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (4.2 m) + sealant	1.00	nr	753.29	113.56	753.29	113.56	866.85
Bill 7 - Opening schedule (doors + windows)	L1-W13 Alu-clad timber window 900 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (3.6 m) + sealant	1.00	nr	636.46	111.86	636.46	111.86	748.32
Bill 7 - Opening schedule (doors + windows)	L1-W14 Alu-clad timber window 600 x 914 S.O., RAL 7016, DGU, trickle vent, handles, aluminium cill; illbruck ME110 internal membrane (3.0 m) + sealant	1.00	nr	519.65	110.16	519.65	110.16	629.81
Bill 8 - Electrical installation	4 double sockets + 4 LED battens, sub-board, short feed, test + cert	1.00	item	760.00	680.00	760.00	680.00	1,440.00
Bill 9 - Design + approvals (provisional)	Building control (provisional)	1.00	item	650.00	0.00	650.00	0.00	650.00
Bill 9 - Design + approvals (provisional)	Structural engineer - calcs + details (provisional)	1.00	item	850.00	0.00	850.00	0.00	850.00
Bill 9 - Design + approvals (provisional)	Drawings / lawful development certificate (provisional)	1.00	item	1,250.00	0.00	1,250.00	0.00	1,250.00

Bill	Item	Qty	Unit	Supply rate	Install rate	Supply	Install	Total
							BOQ net	51,441.01

Programme - construction time per element (working days)

Element	Days	Note
Site setup + setting out	0.50	welfare, skip, set out the raft
Below ground - excavation, muck away, drainage	3.20	2 operatives + excavator
Footings / substructure - hardcore, DPM, mesh, starter bars	1.00	
Raft pour + power float	1.00	pump on site
Raft cure before the ICF	3.00	minimum before standing the forms (7 days before full load)
ICF install - stand forms, rebar, bracing + alignment	2.00	3-man gang, 4.3 min / form
ICF pour (walls + gables)	1.00	4-man pour gang + pump
ICF cure	1.00	
Strike the bracing + alignment	1.00	alignment hire = 5 working days -> 1 wk
First floor, stair + roof structure	7.50	joists, deck, stair, guarding, ceiling; rafters + glulam ridge, ladders
Roof coverings + rainwater goods	3.20	2 roofers
Doors, windows + opening tapes	2.10	
External finish	7.00	2 operatives (Dryvit - weather dependent, >= 5 C)
Electrics + test	2.50	1 electrician
Snag + clean	0.50	
Total	36.50	about 8 weeks